

Transcript of 2814

Specification for trenching, levelling, forming walks &c in the Church Yard of Logie
Easter 7th Jany 1876.

The standing timber to be cut, and all the stocks, roots &c to be dug up and left on the surface.

The whole area of the ground (with the exception of the walks and Lairs already formed) to be trenched to a depth of not less than 12 inches, and any stones that may be met with must be turned out.

The ground to be neatly levelled, and any existing heights to be regulated and hollows filled up so as to have a uniform surface throughout.

All the rubbish to be removed from the ground to a place which will be pointed out, the distance not to exceed 200 yards.

The building at the back of the Church to be taken down, and if found necessary the joining of its walls with that of the Church must be harled to correspond.

The ash-pit to be filled up to the level of the adjoining ground.

The walks measuring 234 linial yards are to be formed on the lines marked out on the accompanying Plan [*missing*], and to be 5 feet wide having a uniform convexity of two inches in their cross section.

The edge of these walks to be laid with greensward one foot wide, and placed two inches above the finished surface of the walks. The sods to be neatly jointed and firmly pressed with the back of the spade. Any black mould that may be found in the formation of the walks must be carefully laid aside and applied in levelling the surface. The walks are to be covered with 4 inches of Pit or common gravel, free of earthy matter, then covered with one inch of clay and blinded with a sprinkling of fine gravel.

All the Green Paths shown on Plan are to be lined out and formed by the Contractor, and sown with grass seeds.

The stone steps at the East Gate to be removed and the carriage drive banked up to the level of the road and carried up in a uniform manner to join the gravelled space at the end of the Church. It is to be 9 feet 6 inches wide, and formed and gravelled in the same manner as the walks.

A sprinkling of fine gravel to be applied to the road leading from the south gate, and the gravelled space in front of the Church to be raised two inches.

The bank of earth along the dyke side lying southwards from the East gate is to be reduced one foot or fifteen inches if the foundation will permit, and the earth removed therefrom to be used in the Burying-ground.

After the walks are formed, and the ground levelled as above described the Contractor is to sow 5 Bushels of Lawn Grass seeds, and afterwards to roll the ground in the usual way.

The Contractor to supply all tools, materials, cartages &c that may be necessary for the due execution of the above specified works, and to complete the same in a neat substantial and workmanlike manner in terms of this specification, and to the entire satisfaction of the Employers or anyone appointed by them to inspect the work on or before the thirty first day of March Eighteen hundred and seventy six years.

The foregoing specification written and subscribed on this and the five preceding pages forms the specification referred to in the Contract entered into between us for certain repairs upon the Church Yard of Logie Easter. In witness whereof this docquet

Helen Graham Mackenzie
Robert Ross

Witness
Witness

John Matheson
Alexander Mackenzie